

**Name of work: SOLING, METALING AND BITUMEN WORK FOR THE CONSTRUCTION OF VEHICLE PARKING YARD AT PALAKKAD DAIRY, KALLEPPULLY, PALAKKAD DIST**

SL NO	QTY	ITEM DESCRIPTION	UNIT	RATE (Rs)	AMOUNT (Rs)
1.	250	Clearing of light jungle including up rooting of thick vegetation and small trees of girth up to 30cm and removal of rubbish up to a distance of 150m outside the periphery of the area cleared.	Sqm		
2.	1	Felling trees including cutting of trunks and branches, removing roots completely and stacking	Nos		
3.	100	Earth work excavation in all kinds of soil for leveling the area for metaling for widening of road including all cost conveyance and all labour charges etc.	Cum		
4.	300	Earth work excavation in all class soil for filling with contractors own earth for formation of road including all cost conveyance and all labour charges etc.	Cum		
5.	300	Consolidating the earth in layers of 15cm using power roller including all cost of conveyance and all labour charges etc.	Cum		

6.	3450	Metaling the road way 100mm spread thickness compacted to 75mm using broken stone of 60mm & 36mm and blinding material sand bed rolling to dry compacting with power roller	Sqm
7.	1650	Providing 20mm chipping carpet over WBM surface with broken stone after Thorough cleaning the base with brushes Brass brooms etc.	Sqm
8.	300	Collection and supply of gravelly red earth Stacking on road side as per std. Specification	Cum
9.	175	Collection and supply of 60mm and 36mm graded metal (7:3) from approved quarry and stacking on road side as per specifict	Cum
11.	175	Collection and supply of 36mm graded metal from approved quarry and stacking on road side as per std specification.	Cum
12.	40	Collection and supply of 12mm graded metal from approved quarry and stacking on road side as per std specification	Cum
13.	15	Collection and supply of 6mm graded metal from approved quarry and stacking on road side as per std specification	Cum

14.	1500	Sectioning up to 150mm thick for forming the surface	Sqm
15	150	Providing and fixing RCC/CC (1:2:4) precast kerb stone of size 75mm to 100 mm thick 300mm deep and 600mm long as per architects drawing including excavations, PCC of joins and white or colour washing etc. complete as per technical specification	RM
16.	Item	Providing 20mm chipping carpet over existing BT surface with broken stone after Thorough cleaning the base with brushes Brass brooms etc.	Sqm
17.	Item	Providing Bitumen seal coat over chipping carpet with 6mm metal as per std specification	Sqm

-----  
**Note: Rate should be quoted in words as well as in figures**

**TOTAL**