

**Kerala Co-operative Milk Marketing Federation Limited****Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651**

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

No: CFP-M/PROD/107/2023

28.01.2023

Quotation Notice

Sealed quotations are invited from experienced contractors for dismantling old structural steels and sheets inside plant (godown, maize area, boiler) at cattle feed plant, Malampuzha.

SCOPE OF WORK

SL. NO	Description of work	Qty	Unit rate (Rs.)	Total (Rs.)
1.	Dismantling carefully the existing galvalume sheeted roof and stacking the same within the premises up to 500 meter as per the direction of engineer in charge.	176.7 m ²		
2.	Dismantling carefully the existing roof structural I section beam 200 x 100 mm and stacking the same within the premises up to 500 meter as per the direction of engineer in charge.	7.5 meter		
3.	Providing and fixing roof structural I section beam 100 x 50 mm with sufficient base plate as per the direction of engineer in charge.	4 meter		
4.	Demolishing cement concrete manually / by mechanical means including disposal of material within 100 metres lead as per direction of Engineer- in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.2 m ³		
5.	Providing and fixing 2.5 inch (CPVC) / GI pipes for laying electrical cable, This includes jointing of pipes & fittings, with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc.	14 meter		
6.	Dismantling carefully the existing Canopy (2nos) roof structural (angles , column, beam, channels, base plates different size) and stacking the same within the premises up to 500 meter as per the direction of engineer in charge.	130 m ²		
7.	Providing and fixing UPVC pipes, having thermal stability for hot & cold water supply, including all UPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings, with one step UPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 3/4 inch diameter	15 meter		
8	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement,	0.5 m ³		



Kerala Co-operative Milk Marketing Federation Limited

Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

	including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer - in-charge. Note:- Cement content considered in this item is @ 330 kg/cum. Excess or less cement used as per design mix is payable or recoverable separately. All work above plinth level up to floor V level			
9	Solid masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 20cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	0.85 m ³		
10	12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	12.54 m ²		
11	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	12.54 m ²		
12	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	1.26 m ³		
13	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement : 6 coarse sand)	2.42 m ³		
14	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar.	0.32 m ³		
TOTAL				
Unforeseen items				
GST				
GRAND TOTAL				

General Conditions

1. Applicable statutory deductions like GST, income tax, sales tax, EPF/ ESI, Work contract tax, etc. shall be effected while settling bills. The contractors must remit ESI/EPF for the work and for their employees should produce proof of remittance to avoid the ESI cutting while submitting the bills. Submit the challan as the proof of remittance along with bills, for considering release of payment. Without the ESI/EPF remittance proof payments will be released only after cutting the ESI/EPF from the bills.
2. All essential materials required for the work shall be brought to the site before commencing the work.
3. Specifications shall be as mentioned in the schedule of quantities. In case for clarification, our Engineer shall be contacted before taking up the particular work.



Kerala Co-operative Milk Marketing Federation Limited

Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

4. The quantities and items of works mentioned in the schedule are tentative. Manager reserves the right to place work order for part of the schedule, depending upon the financial implications. Payment shall be effected only for those quantities actually executed at site.
5. The materials shall be inspected by our engineers before acceptance. The materials shall be of government approved make.
6. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such labourers will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Cattle Feed Plant's property, the contractor alone shall be liable.
7. Income tax, ESI and other applicable statutory deductions shall be affected while settling bills.
8. The plant day to day activities should not be affected during the course of work.
9. The work found inferior in quality/ bad workmanship the same shall be redone at contractor's risk and cost.

EARNEST MONEY DEPOSIT

1. The offer should be accompanied by an EMD of Rs.2,500 /-(Rupees Two Thousand five hundred Only).
2. The EMD shall be in the form of cash or demand draft drawn in favour of Manager, Kerala Co-operative Milk Marketing Federation Limited, Palakkad.
3. Offers without EMD are liable to be rejected, No EMD exemption is applicable.
4. The EMD of the unsuccessful quotationers will be released on finalisation of the contract. The EMD of the successful quotationer will be released only after satisfactory completion of the work in all respects.
5. No interest will be paid for the EMD for the period for which it lies with the KCMMF.

Terms and Conditions

1. The contractor shall provide all the material, tools and tackles required for the works.
2. The entire works shall be completed within 60 days from the date of receipt of the order.
3. Quotationer should submit the id proof copy along with the quotation and self attested copy of the bidders valid registration certificate in Kerala PWD / Irrigation.
4. The contractor must have minimum 5 years work experience in similar works.
5. The contractor shall guarantee to rectify any defect noticed in works due to bad workmanship within 6 month from the date of completion of the work.
6. All safety measures shall be taken for the work like including safety belts, scaffolding's etc. work permit shall be taken before the commencement of work. All risk shall be covered by contractor as per norms.
7. Payment terms: 100% after completion of entire work.
8. Pre-Bid meeting: 31-01-2023, 11:00 AM contractor shall attend the Pre-Bid meeting for participate the tender.

The sealed super scribed offer must be submitted on or before 02.02.2023 03:00 pm to the Manager, Cattle feed plant, Malampuzha, and will be opened at 3:30 P.M. on the same day.

The undersigned reserves the right to accept any or reject all the quotations without assigning any reason.

Thanking you,
Yours faithfully,

MANAGER

Copy to: FO, DE (P& M)

To, 1.All Notice Boards 2. Panchayath Office 3.Milma website 4. Village office 5. Publish in local daily