



milma

Kerala Co-operative Milk Marketing Federation Limited

Cattle Feed Plant, Malampuzha, Palakkad - 678651

Phone: 0491-2816301 Website: www.milma.com, E mail: cfm@milma.com

KCMMF / CFM-UHO / PRODUCTION (588) / BATCHMIXER & BLOWER DUCTLINE / 2023 - 24 / 2484 / 24.11.2023 (TRUE COPY)

QUOTATION NOTICE

Sealed price quotations are invited from experienced Mechanical Fabrication Contractors for the following repair and rectification works at Milma, Cattle Feed Plant, Malampuzha, Palakkad – 678651, KERALA.

I. DESCRIPTION OF WORKS:

Sl. No.	Description of work	Qty.	Budgetary Estimate
1	FIXING OF BATCH MIXER INNER RIBS, OUTER RIBS AND SUPPORTING ROD (STUMP) ON THE BATCH MIXER ROTER (a) Work includes removing all broken bolt from the bush fixed on the rotor shaft and fix a required number of new threaded bush on the shaft (b) Approximately 7 inner ribs of size 125 cm L x 4 cm W x 10 mm T; 7 outer ribs of size 125cm L x 4 cm W x 10 mm T; Rib mounting Rods (Stumps) of size 70 cm L x 3.5 cm Dia. along with the supply of required number of rib fixing plates with hole is at contractor's scope.	1 SET	
2	SUPPLY AND FIXING 2.50 m L x 1 m x 50 cm RECTANGLE DUCTING PIPELINE, BY USING 3 mm thick MS (or) SS PLATE WITH NECESSARY FLANGES (a) Work includes dismantling of damaged blower ducting from existing ducting line (b) Fabricating fixing new ducting with necessary flanges and drain plug by using 2" threaded GI Pipe (c) Apply one coat of metal primer and two coats of enamel paint on the fabricated item by using reputed make of paint (d) Rate for SS and MS will be collected separately	1 SET	

II. GENERAL TERMS AND CONDITIONS:

1. Applicable statutory deductions like GST, income tax, sales tax, EPF/ESI, Work contract tax, etc. shall be effected while settling bills. The contractors must remit ESI/EPF for the work and for their employees should produce proof of remittance to avoid the ESI cutting while submitting the bills. Submit the challan as the proof of remittance along with bills, for considering release of payment. Without the ESI/EPF remittance proof, payments will be released only after recovering the statutory ESI/EPF from the respective bills.
2. All essential materials MS or SS Sheets, MS Angles and MS or SS Flat etc. required for the work shall be brought to the site before commencing the work.
3. Specifications shall be as mentioned in the schedule of work quantities. In case for clarification, our Engineer shall be contacted before taking up the particular work.
4. The quantities and items of works mentioned in the schedule are tentative. Manager reserves the right to place work order for part of the schedule, depending upon the financial implications. Payment shall be effected only for those quantities actually executed at site.
5. The materials shall be inspected by our engineers before acceptance. The materials shall be of our approved make as per the schedule.
6. Each item of work shall be approved prior to commencement of the next work.
7. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed Plant shall not be liable for any benefits/compensation to the workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall provide suitable safety measures to their Workers and also the plant raw materials stored in that area in case of any emergency like rain/ wind etc..
8. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such labourers will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Cattle Feed Plant's property, the contractor alone shall be liable.
9. Income tax, ESI and other applicable statutory deductions shall be mandatorily effected while settling bills.
10. The plant day to day activities should not be affected during the course of work.
11. The work done if found to be inferior in quality or reveals bad workmanship, the same shall be redone at contractor's risk and cost.
12. Your price quotation shall include Transportation charges, Labour charges, Material cost, Loading / Unloading charges and Other incidental expenses if any. So nothing extra will be paid apart from the quoted rate later.

III. OTHER TERMS & CONDITIONS:


1. The fabrication contractor shall provide all the fabrication materials and consumables, nuts, bolt, packing material, welding rods, Emery cloth, painting materials etc. required for the works.
2. The fabrication contractor shall bring the tools and tackles required for the works.

3. **The entire works shall be completed within 5 days from the date receipt of the job order.**
4. All the works shall be carried out as per the directions of our plant engineer.
5. The contractor shall guarantee to rectify any defect noticed in works due to bad workmanship within six months from the date of completion of the work.
6. All safety measures shall be taken for the work like including safety belts, scaffolding's etc. Work permit shall be taken before the commencement of work. All risk shall be covered by contractor as per norms.
7. Our bankers are : **SBI PALAKKAD / CANARA BANK MALAMPUZHA**
8. **Any legal disputes* regarding the job order execution shall be under the Palakkad jurisdiction.**

Two copies of quotation notice (True Copy & Duplicate copy) are being sent. The rates inclusive of all shall be mentioned against each work description as given in the quotation format attached herewith. True copy and your sealed offer quotation must be submitted with your office seal and signature of authorized person by postal only, on or before **05.12.2023 3.00 pm**, addressed to the **Manager, Milma, Cattle Feed Plant, Malampuzha** and the received quotations will be opened at **3.30 pm** on the same day. Duplicate copy shall be safely kept at your end for future reference.

The undersigned reserves the right to accept any or reject all the quotations without assigning any reason.

Copy to: **Finance Officer
Office File**





MANAGER

**MANAGER
K.C.M.M.F. LTD.
CATTLE FEED PLANT
MALAMPUZHA. PIN-678 051**

QUOTATION FORMAT

Quotation Reference No: **KCMMF / CFM-UHO / PRODUCTION (588) / BATCHMIXER & BLOWER DUCTLINE / 2023 - 24 / 2484 / 24.11.2023**

1	Name & Address of the Bidder			
2	Company Registration No:			
3	GST Registration No:			
4	ESI Registration No:			
5	Details of Experience			
6	Contact Details (Phone No: & email ID)			
Sl. No.	Description of work	Qty.	Budgetary Estimate	



Sl. No.	Description of work	Qty.	Budgetary Estimate
1	<p>FIXING OF BATCH MIXER INNER RIBS, OUTER RIBS AND SUPPORTING ROD (STUMP) ON THE BATCH MIXER ROTER</p> <p>(c) Work includes removing all broken bolt from the bush fixed on the rotor shaft and fix a required number of new threaded bush on the shaft</p> <p>(d) Approximately 7 inner ribs of size 125 cm L x 4 cm W x 10 mm T; 7 outer ribs of size 125cm L x 4 cm W x 10 mm T; Rib mounting Rods (Stumps) of size 70 cm L x 3.5 cm Dia. along with the supply of required number of rib fixing plates with hole is at contractor's scope.</p>	1 SET	
2	<p>SUPPLY AND FIXING 2.50 m L x 1 m x 50 cm RECTANGLE DUCTING PIPELINE, BY USING 3 mm thick MS (or) SS PLATE WITH NECESSARY FLANGES</p> <p>(e) Work includes dismantling of damaged blower ducting from existing ducting line</p> <p>(f) Fabricating fixing new ducting with necessary flanges and drain plug by using 2" threaded GI Pipe</p> <p>(g) Apply one coat of metal primer and two coats of enamel paint on the fabricated item by using reputed make of paint</p> <p>(h) Rate for SS and MS will be collected separately</p>	1 SET	

Note: Separate rates can be quoted for using MS or SS type materials

Place:

Date:

Signature:

Name:

Address:

Company Seal: