



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

No: CFP-M/PROD/588/2022

14.10.2022

Quotation Notice

Sealed quotations are invited from experienced civil contractors for new security cabin works at cattle feed plant Malampuzha.

SCOPE OF WORK

| Sl no | Particulars | No. | L | B | H | Qty. | Unit rate | Amount (Rs) |
|-------|--|------|------|------|------|----------------|-----------|-------------|
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. | | | | | | | |
| | Pillar | 4.00 | 1.20 | 1.20 | 1.20 | 6.91 | | |
| | For dry rubble packing | 2.00 | 1.70 | 0.45 | 0.45 | 0.69 | | |
| | | 2.00 | 3.08 | 0.45 | 0.45 | 1.25 | | |
| | | | | | | 8.85 m3 | | |
| 2 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size) | | | | | | | |
| | PCC | 4.00 | 1.20 | 1.20 | 0.10 | 0.58 | | |
| | floor | 1.00 | 4.00 | 2.50 | 0.10 | 1.00 | | |
| | | | | | | 1.58 m3 | | |
| 3 | DR masonry - Dry rubble without concrete leveling course masonry with good quality blasted rubble including packing to compactness to line and levels cost and conveyance of all materials labour charges etc. Complete as per direction of department officers at site. | | | | | | | |
| | dry rubble packing | 2.00 | 3.00 | 0.45 | 0.45 | 1.22 | | |
| | | 2.00 | 3.90 | 0.45 | 0.45 | 1.58 | | |
| | | | | | | 2.79 m3 | | |
| 4 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) | | | | | | | |
| | Footing | 4.00 | 1.30 | 1.30 | 0.30 | 2.03 | | |
| | pillar up to plinth beam | 4.00 | 0.80 | 0.23 | 0.30 | 0.22 | | |
| | plinth beam | 2.00 | 3.00 | 0.30 | 0.45 | 0.81 | | |
| | do | 2.00 | 3.90 | 0.30 | 0.45 | 1.05 | | |
| | | | | | | 4.11 m3 | | |
| 5 | Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete | | | | | | | |
| | footing | 4.00 | 5.20 | 0.30 | | 6.24 | | |
| | pillar | 4.00 | 1.06 | 0.80 | | 3.39 | | |
| | plinth beam | 2.00 | 3.00 | 1.20 | | 7.20 | | |



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAAK5375M6ZB

| | | | | | | |
|----|--|-------------|------|------|--------|-----------|
| | | 2.00 | 3.90 | 1.20 | | 9.36 |
| | | | | | | 26.19 m3 |
| 6 | Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more | | | | | |
| | | 4.11 | 100 | | | 411.18 kg |
| 7 | Solid block masonry using precast solid block (factory made) of size 40x20x15 cm or nearest available size coming IS 2185 part 1 of 1979 for superstructure above floor two level up to floor five level with thickness 15 cm in CM 1:6(1 cement : 6 course sand) etc. complete | | | | | |
| | wall | 2.00 | 4.40 | 0.20 | 2.85 | 5.016 |
| | do | 2.00 | 2.50 | 0.20 | 2.85 | 2.85 |
| | steps | 2.00 | 1.00 | 0.30 | 0.20 | 0.12 |
| | Deduction | -1.00 | 0.90 | 0.20 | 2.10 | -0.378 |
| | Window | -3.00 | 1.00 | 0.20 | 1.35 | -0.81 |
| | | | | | | 6.798 m3 |
| 8 | Reinforced cement concrete work in arches, archribs, domes, vaults, shells, folded plate and roofs having slope more than 15 up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement :1.5 coarse sand(Zone III) : 3 graded stone aggregate 20 mm nominal size) | | | | | |
| | lintel | 2.00 | 4.40 | 0.20 | 0.15 | 0.26 |
| | do | 2.00 | 2.50 | 0.20 | 0.15 | 0.15 |
| | slab | 2.00 | 3.98 | 2.00 | 0.10 | 1.59 |
| | | 2x2x0. 5 | 4.10 | 2.00 | 0.10 | 1.64 |
| | | | | | | 3.65 m3 |
| 9 | Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo - Mechanically Treated bars of grade Fe-500D or more | | | | | |
| | | 3.65 | | | 100.00 | 364.6 kg |
| 10 | Centering and shuttering including strutting, etc. and removal of form for:Suspended floors, roofs, landings, balconies and access platform | | | | | |
| | lintel | 2.00 | 4.40 | 0.30 | | 2.64 |
| | | 2.00 | 2.50 | 0.30 | | 1.50 |
| | slab | 2.00 | 3.98 | 2.00 | | 15.92 |
| | | 2x2x0. 5 | 4.10 | 2.00 | | 16.40 |
| | | | | | | 36.46 m2 |
| 11 | 12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand) | | | | | |
| | wall | 2.00 | 4.40 | 2.85 | | 25.08 |
| | | 2.00 | 2.90 | 2.85 | | 16.53 |
| | basement | 2.00 | 4.55 | 0.45 | | 4.10 |
| | | 2.00 | 3.05 | 0.45 | | 2.75 |



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

| | | | | | | |
|----|--|-------------|-------|------|------|------------------|
| | inside | 1.00 | 13.00 | 2.85 | | 37.05 |
| | ceiling | 2.00 | 3.98 | 2.00 | | 15.92 |
| | | 2x2x0. 5 | 4.10 | 2.00 | | 16.40 |
| | roof top | 2.00 | 3.98 | 2.10 | | 16.72 |
| | | 2x2x0. 5 | 4.10 | 2.10 | | 17.22 |
| | Deduction door | -1.00 | 0.90 | 2.10 | | -1.89 |
| | Window | -3.00 | 1.00 | 1.35 | | -4.05 |
| | | | | | | 145.82 m3 |
| 12 | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately):For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) | | | | | |
| | Window | 3.00 | 4.70 | | 1.11 | 15.651 |
| | Door frame | 1.00 | 6.00 | | 1.11 | 6.66 |
| | | | | | | 22.31 kg |
| 13 | For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) | | | | | |
| | Window | 6.00 | 3.50 | | 0.97 | 20.37 |
| | Door frame | 1.00 | 5.60 | | 0.97 | 5.43 |
| | | | | | | 25.80 m2 |
| 14 | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness | | | | | |
| | shutter | 6.00 | 0.45 | 1.30 | | 3.51 |
| | door | 1.00 | 0.80 | 1.10 | | 0.88 |
| | | | | | | 4.39 m2 |
| 15 | Providing and fixing 12 mm thick prelaminate particle board flat pressed three layer or graded wood particle board conforming to IS : 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in - Charge. Pre- laminated particle board | | | | | |



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAAK5375M6ZB

| | | | | | | |
|----|--|---------|-------|------|--|-------------------------|
| | with decorative lamination on both sides | | | | | |
| | door | 1.00 | 0.80 | 0.90 | | 0.72 m2 |
| 16 | Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600 x 600 mm. | | | | | |
| | floor | 1.00 | 2.50 | 4.00 | | 10.00 |
| | steps | 2.00 | 1.00 | 0.50 | | 1.00 |
| | | | | | | 11.00 m2 |
| 17 | Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :13.48.1 Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of special primer applied @ 0.75 ltr /10 sqm | | | | | |
| | wall | 2.00 | 4.40 | 2.85 | | 25.08 |
| | | 2.00 | 2.90 | 2.85 | | 16.53 |
| | basement | 2.00 | 4.55 | 0.45 | | 4.10 |
| | | 2.00 | 3.05 | 0.45 | | 2.75 |
| | inside | 1.00 | 13.00 | 2.85 | | 37.05 |
| | ceiling | 2.00 | 3.98 | 2.00 | | 15.92 |
| | | 2x2x0.5 | 4.10 | 2.00 | | 16.40 |
| | roof top | 2.00 | 3.98 | 2.10 | | 16.72 |
| | | 2x2x0.5 | 4.10 | 2.10 | | 17.22 |
| | Deduction door | -1.00 | 0.90 | 2.10 | | -1.89 |
| | Window | -3.00 | 1.00 | 1.35 | | -4.05 |
| | TOTAL | | | | | 145.82 m2 |
| | | | | | | Unforeseen items |
| | | | | | | Total |
| | | | | | | GST @18% |
| | | | | | | Net total |

General Conditions

1. Applicable statutory deductions like GST, income tax, sales tax, EPF/ ESI, Work contract tax, etc. shall be effected while settling bills. The contractors must remit ESI/EPF for the work and for their employees should produce proof of remittance to avoid the ESI cutting while submitting the bills. Submit the challan as the proof of remittance along with bills, for considering release of payment. Without the ESI/EPF remittance proof payments will be released only after cutting the ESI/EPF from the bills.
2. All essential materials required for the work shall be brought to the site before commencing the work.
3. Specifications shall be as mentioned in the schedule of quantities. In case for clarification, our Engineer shall be contacted before taking up the particular work.



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

4. The quantities and items of works mentioned in the schedule are tentative. Manager reserves the right to place work order for part of the schedule, depending upon the financial implications. Payment shall be effected only for those quantities actually executed at site.
5. The materials shall be inspected by our engineers before acceptance. The materials shall be of government approved make.
6. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such labourers will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Cattle Feed Plant's property, the contractor alone shall be liable.
7. Income tax, ESI and other applicable statutory deductions shall be effected while settling bills.
8. The plant day to day activities should not be affected during the course of work.
9. The work found inferior in quality/ bad workmanship the same shall be redone at contractor's risk and cost.

EARNEST MONEY DEPOSIT

1. The offer should be accompanied by an **EMD of Rs.4,500/- (Rupees Four Thousand five hundred Only)**.
2. The EMD shall be in the form of cash or demand draft drawn in favour of Managing Director, Kerala Co-operative Milk Marketing Federation Limited.
3. Offers without EMD are liable to be rejected, No EMD exception is applicable.
4. The EMD of the unsuccessful quotationers will be released on finalisation of the contract. The EMD of the successful quotationer will be released only after satisfactory completion of the work in all respects.
5. No interest will be paid for the EMD for the period for which it lies with the KCMMF.

Terms and Conditions

1. The contractor shall provide all the material, tools and tackles required for the works.
2. The entire works shall be completed within 60 days from the date receipt of the order.
3. Quotationer should submit the id proof copy along with the quotation and self attested copy of the bidders valid registration certificate in Kerala PWD / Irrigation.
4. The contractor must have minimum 5 years work experience in similar works.
5. The contractor shall guarantee to rectify any defect noticed in works due to bad workmanship within **6 month** from the date of completion of the work.
6. All safety measures shall be taken for the work like including safety belts, scaffolding's etc. work permit shall be taken before the commencement of work. All risk shall be covered by contractor as per norms.
7. Payment terms: 50% advance payment against material supply and balance 50% after completion of entire work.

The sealed **super scribed** offer must be submitted on or before 21.10.2022 03:00 pm to the Manager, Cattle feed plant, Malampuzha, and will be opened at 3:30 P.M. on the same day.

The undersigned reserves the right to accept any or reject all the quotations without assigning any reason.

Thanking you,
Yours faithfully,

MANAGER

Copy to: FO, DE (P& M)

To,

1. All Notice Boards 2. Panchayath Office 3. Milma website 4. Village office