



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

No: CFP-M/PROD/588/2022

24.09.2022

Quotation Notice

1. Kerala Co-operative Milk Marketing Federation Ltd. invite sealed quotations for the repair and maintenance of silo top distribution conveyor & silo elevator gravity pipe changing and related works at Cattle Feed Plant, Malampuzha. Interested Bidders may obtain further information from the office of Cattle Feed Plant, Malampuzha during working hours 10 AM – 4PM on all working days.
2. Detailed terms and conditions, scope of work etc. as indicated below for reference.

Bid Reference	No: CFP-M/PROD/588/2022 Dt: 24.09.2022
Name of work	Repair and maintenance of silo top distribution conveyor & silo elevator gravity pipe changing and related works
Place of work	Cattle Feed Plant, malampuzha, Palakkad.
Last date of submission	30.09.2022 at 3.00pm
Date of opening	30.09.2022 at 3.30pm
Address for communication and Place of bid opening	Cattle Feed Plant, Malampuzha, Palakkad-678651
Bid Validity	30 days from 30.09.2022

Scope of work

Sl. No.	Work Description	Qty
1	Silo elevator old gravity pipe dismantling MS 5 meter 12 inch dia	1 no
2	Installation of silo elevator new gravity pipe MS 5 meter 12 inch dia The work includes erection of MS pipe with proper welding as per site condition.	1 no
3	Supply and erection of platform including hand rail for silo elevator top to silo top conveyor. For attending maintenance of gravity pipe. Platform details Width: 2 feet Length: 16 feet Handrail height: 3 feet in both side. The work includes supply of all required material and erection as per the site condition.	1 set
4	Dismantling of silo distribution conveyor (18.5 meter) top and bottom old MS flat as listed below. 1. 25x10 mm – 37 meter 2. 100x10 mm- 37 meter The works includes removing of drag chains, sprockets, motor, conveyor top cover, middle cover from the conveyor.	1 set



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAAK5375M6ZB

5	Supply and fixing of silo distribution conveyor bottom plate. 1. 3mm x 217mm x 18.2 meter MS SHEET The work includes supply of all material and fixing using proper welding to arrest the leakage of the conveyor.	1 set
6	Erection of new MS flat in Silo distribution conveyor (18.5 meter) top and bottom as listed below. 1. 25x10 mm- 37 meter 2. 100x 10 mm- 37 meter The works includes fixing the above MS flat inside top & bottom of the conveyor as per standard, and fixing the drag chains, sprockets, top , middle cover etc.	1 set
7	Modification and height adjustment in existing silo roof top conveyor canopy. Existing canopy size. 1. Height: 920 mm 2. Width : 640 mm 3. Length: 19 meter Required size: 1. Height: 1500 mm 2. Width : 640 mm 3. Length: 19 meter The work including supply of required material and modification of canopy into removable type with height adjustment as per the site condition	1 set

General Conditions :

1. Applicable statutory deductions like GST, income tax, sales tax, EPF/ ESI, Work contract tax, etc. shall be effected while settling bills. The contractors must remit ESI/EPF for the work and for their employees should produce proof of remittance to avoid the ESI cutting while submitting the bills. Submit the chelan as the proof of remittance along with bills, for considering release of payment. Without the ESI/EPF remittance proof payments will be released only after cutting the ESI/EPF from the bills.
2. All essential materials required for the work shall be brought to the site before commencing the work.
3. Specifications shall be as mentioned in the schedule of quantities. In case for clarification, our Engineer shall be contacted before taking up the particular work.
4. The quantities and items of works mentioned in the schedule are tentative. Manager reserves the right to place work order for part of the schedule, depending upon the financial implications. Payment shall be effected only for those quantities actually executed at site.
5. The materials shall be inspected by our engineers before acceptance. The materials shall be of our approved make as per the schedule.
6. Each item of work shall be approved prior to commencement of the next work.
7. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed Plant shall not be liable for any benefits/compensation to the workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha P.O., Palakkad-678 651

Tel: 0491-2816316, 2816317, E-mail: cfm@milma.com

GST No.32AAAK5375M6ZB

- provide suitable safety measures to their Workers and also the plant raw materials stored in that area in case of any emergency like rain/ wind etc.
8. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such labourers will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Cattle Feed Plant's property, the contractor alone shall be liable.
 9. Income tax, ESI and other applicable statutory deductions shall be affected while settling bills.
 10. The plant day to day activities should not be affected during the course of work.
 11. The work found inferior in quality/ bad workmanship the same shall be redone at contractor risk and cost.

Terms and Conditions:

1. The contractor shall provide all material required for the works as per the schedule. Gravity pipe MS 12 inch and MS flat 25 x10mm, 100x10mm will be provide by us.
2. The contractor shall supply tools and tackles (welding machine, gas cutter, oxygen LPG, all necessary tools) required for the works.
3. **The entire works shall be completed within 30 days from the date receipt of the order.**
4. All the works shall be carried out as per the directions of our plant engineer.
5. The contractor shall guarantee to rectify any defect noticed in works due to bad workmanship within six months from the date of completion of the work.
6. All safety measures shall be taken for the work like including safety belts, scaffolding's etc for height work up to 30 meter. work permit shall be taken before the commencement of work. All risk shall be covered by contractor as per norms.
7. Payment terms: 100% payment against the completion of all above work against original invoice.
8. Our bankers are : **SBI PALAKKAD / CANARA BANK MALAMPUZHA**

The sealed **super scribed** offer must be submitted on or before **30.09.2022, 03:00 PM** to The Manager, Cattle feed plant, Malampuzha, and will be opened at **3:30 PM** on the same day.

The undersigned reserves the right to accept any or reject all the quotations without assigning any reason.

Thanking you,
Yours faithfully,


MANAGER

Copy to: AO, DE (P&M)

To,

1. All Notice Boards
2. Panchayath Office
3. Milma website
4. Village office