



**KERALA CO-OPERATIVE MILK MARKETING FEDERATION LIMITED  
CATTLE FEED PLANT, MALAMPUZHA, PALAKKAD – 678651**

**Tel: 0491 - 2816317, 2816301 E mail: [cfm@milma.com](mailto:cfm@milma.com), [cfmprod@milma.com](mailto:cfmprod@milma.com)**

---

**CFPM/PROD/588/WD/2024/1072**

**02/09/2024**

---

**Notice inviting tender for supply and installation of 1000 litre capacity  
Water Tank at Milma Cattle Feed Plant, Malampuzha**

Sealed quotations are invited from experienced Plumbing Contractors for the supply and installation of a 1000 litre capacity water tank along with necessary plumbing accessories for providing separate drinking water distribution system at Milma Cattle Feed Plant, Malampuzha using the KWA water source.

**SCOPE OF WORKS**

- 1) Supply and installation of 1000 litre capacity water tank with float switch above our old workers amenity building block
- 2) Laying a separate water line from KWA incoming point to the installed new tank
- 3) Laying a separate distribution line from new tank to our Canteen building, Production Plant premises and Administrative building block with necessary control valves.

Detailed scope of works and the necessary items required for the above are mentioned in the **Annexure - 1** enclosed herewith.

**GENERAL CONDITIONS**

1. Applicable statutory deductions like GST, Income tax, sales tax, EPF/ESI, work contract tax, etc, shall be effected while settling bills. The contractors must remit ESI/EPF for the work and for their employees should produce proof of remittance to avoid the ESI cutting while submitting the bills. Submit the Chelan as the proof of remittance along will bills, for considering release of payment. Without the ESI/EPF remittance proof payments will be released only after cutting the ESI/EPF from the bills.
2. All essential materials required for the work shall be brought to the site before commencing the work.
3. Specification shall be as mentioned in the schedule of quantities and for further clarification our Production Section Head shall be contacted before taking up the particular work.

4. The quantities and items of works mentioned in the schedule are tentative. Manager reserves the right to place work order for part of the schedule, depending upon the financial implications. Payment shall be effected only for those quantities actually executed at site.
5. Each item of work shall be approved prior to commencement of the next work.
6. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed plant shall not be liable for any benefits/compensation to the workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall provide suitable safety measures to his workmen and also to the plant raw materials stored in that area in case of any emergency like rain/wind etc. while executing the work.
7. The contractor or his workmen shall not interfere in any activity of the plant and/or cause any damages to building/property. The entry of all such laborers will be on the basic of gate pass, which will have to be arranged by the contractor prior to starting the work. In the event of any damage to Cattle feed Plant's property, the contractor alone shall be liable.
8. The plant day to day activities shall not be affected during the execution of contract works.
9. The contract works found inferior in quality/of bad workmanship shall be redone at contractor's risk and cost within in stipulated time. Financial losses incurred due to delayed execution of contract works affecting our routine production will be suitably recovered from the contractor.

#### **OTHER TERMS AND CONDITIONS**

1. Work contract tax, E.S.I contribution, GST and other statutory recoveries if any shall be deducted from the bill by us if the contractor does not comply with statutory deductions rules.
2. All the works shall be carried out as per the direction of our production section head and shall follow the safety regulations of our company.
3. You shall guarantee to rectify any defects noticed in your works due to bad workmanship within 12 months from the date of completion of the work contract. ***An under taking in this regard shall be submitted along with your invoice for effecting payment.***
4. You shall quote the rates of those pipes, water tank and associated other plumbing accessories of ISI stamped and of approved Manufactures only.
5. The bidder shall submit copies of GST registration certificate & valid ID proof along with other details as required in the Annexure - 1 enclosed.
6. Duly filled in quotation shall be submitted in sealed cover on or before 3:00 PM On 25.09.2024 and will be opened at 3.30 PM on the same day.

The sealed quotation shall be addressed and sent to:

The Manager,  
KCMMF - Milma,  
Cattle Feed Plant,  
Malampuzha,  
Palakkad - 678651

***Mail quotations will not be accepted strictly.***

The undersigned reserves the right to accept any or reject all the quotations without assigning any reason.

Yours faithfully,

MANAGER

Copy to: FO, Production Section File, Office File

1. All Notice Boards
2. Canara Bank
3. Panchayath Office
4. Milma website

## ANNEXURE – 1

### FORMAT FOR QUOTATION SUBMISSION

**Enquiry No: CFPM/PROD/588/WD/2024/02.09.2024**

1	Name & Address of the Bidder	
2	Company Registration No.	
3	GST Registration No: (Enclose photocopy GST Registration Certificate)	
6	Aadhar/PAN: (Enclose photocopy of Aadhar/PAN as ID proof)	
7	Contact Details (Phone No. & email ID)	

Sl. No.	Description of Items / Works	Make	Qty	Rate	Amount
1	Supply and installation of 1000 litre capacity water tank above the roofing of Workers Amenity Block - 1		1 no.		
2	Supply of 2 inch tank Connector		1 no.		
3	Supply of 2 inch Ball valve		1 no.		

4	Supply of 2 inch Elbow		12 nos.		
5	Supply of 2 inch Tee		10 nos.		
6	Supply of 2 inch Elbow 45*		10 nos.		
7	Supply of 2 inch Clamp		20 nos.		
8	Supply of 2 inch PVC Pipe 4kg		25 metre		
9	Supply of 2 x 1 inch Reducer		3 nos.		
10	Supply of 2 x 1 inch Bush		3 nos.		
11	Supply of 2 inch Coupler		6 nos.		
12	Supply of 1 inch PVC pipe 10 kg		225 metre		
13	Supply of 1 inch Tee		8 nos.		
14	Supply of 1 inch Elbow		60 nos.		
15	Supply of 1 inch Elbow 45*		20 nos.		
16	Supply of 1 inch Clamp		40 nos.		
17	Supply of 1 inch Tank connector		1 nos.		
18	Supply of 1 inch Ball Valve		5 nos.		
19	Supply of 3 x ¾ inch Bush		6 nos.		
20	Supply of 1 x ¾ inch Reducer		6 nos.		
21	Supply of 1 inch Coupler		20 nos.		
22	Supply of 1 inch F.T.A		2 nos.		
23	Supply of ¾ inch F.T.A		2 nos.		

24	Supply of ¾ inch pvc Pipe 10kg		75 metre		
25	Supply of ¾ inch Elbow		24 nos.		
26	Supply of ¾ inch Tee		6 nos.		
27	Supply of ¾ inch Elbow 45*		18 nos.		
28	Supply of ¾ inch Clamp		26 nos.		
29	Supply of ¾ inch Ball Valve		4 nos.		
30	Supply of ¾ inch Coupler		16 nos.		
31	Supply of 073 Float Valve ¾ inch		1 no.		
32	Supply of ¾ x ½ inch Elbow Pn 16		6 nos.		
33	Supply of ¾ x ½ inch Reducer Pn 16		4 nos.		
34	Supply of Teflon Tape		6 nos.		
35	Supply of 011 – Long Body Tap		2 nos.		
36	Supply of 013 – Angel Valve		2 nos.		
37	Supply of Bond 250 Ml Tin		8 nos.		
38	Supply of 2 mm Nail Box		2 Box		
39	Supply of 2 inch F.T.A		2 nos.		

**TOTAL COST OF MATERIALS SUPPLIED**

**LABOUR CHARGES**

**Labour charges Include**

- 1) The erection of water tank with float switch above the roofing of workers amenity block-1(in 1<sup>st</sup> floor) with all necessary fittings.

- 2) Laying of required length of suitable size pipes from Kerala Water Authority inlet point at factory premises to the newly erected water tank with necessary fittings.
- 3) Laying of suitable size pipe by from over head tank discharge line to Administrative block ground floor (up to water cooler at AD block) with necessary fittings.
- 4) Laying of suitable size pipe from over head tank to entrance of Plant premises (up to water cooler in the plant) with necessary fittings.
- 5) Laying of suitable size pipe by from over head tank discharge line to canteen block (up to canteen kitchen) with necessary fittings.
- 6) All other related jobs for above mentioned works (i.e. fixing of control valve, water tape, Earth work/clamping for pipe laying etc.)
- 7) Testing and commissioning of water tank, waterline, float switches, input out-put pipelines, control valves, water taps etc.

**COST TOWARDS LABOUR CHARGES**

**GST (if any)**

**TOTAL COST TOWARDS LABOUR CHARGES**

Place:

Signature:

Date:

Name:

Address:

Company seal